



COMSATS University, Islamabad

Sahiwal campus

Works Department

COMSATS Road, Off G.T.Road, Sahiwal
Tel: 040-4305004 Web: www.cuisahiwal.edu.pk

No. COMSATS/SWL/WD/

Dated: February 10, 2022

OFFICE NOTE:

NOTICE INVITING QUOTATION

Sealed quotations are invited by the undersigned on 16.02.2022 at 10:30AM for the following works from the registered PEC firm/contractors. The quotations will be opened at 12:00 PM on the same day in the presence of those bidders who may wish to attend. COMSATS University Islamabad, Sahiwal campus reserves all the rights to reject all quotations at any time prior to the acceptance of quotations. CUI, Sahiwal campus will communicate the grounds for rejection of quotations upon request of any supplier or contractor but not liable to justify those grounds.

Sr.No	Name of work/Description	Unit	Rate (Rs.)
1.	PROVIDING AND LAYING OF TUFF PAVER UNDER BENCHES AREAS PLACED AT PATH BETWEEN MAIN BUILDING TOWARDS EXAMINATION DEPARTMENT.		

Note: - Detail description is at next page

M. Amir Raza
Secretary QOC
CUI, Sahiwal campus

Cc:

1. Director, CUI, Sahiwal.
2. Software Developer for publishing on the website.



COMSATS University, Islamabad

Sahiwal campus

Works Department

COMSATS Road, Off G.T.Road, Sahiwal

Tel: 040-4305004 Web: www.cuisahiwal.edu.pk

PROVIDING AND LAYING OF TUFF PAVER UNDER BENCHES AREAS PLACED AT PATH BETWEEN MAIN BUILDING TOWARDS EXAMINATION DEPARTMENT

Sr. No	Description	Unit	Qty	Rates	Amount	Remarks
	CIVIL WORKS					
1	Leveling, dressing and earth filling i/c compaction complete in all respect.	P. Cft	720			
2	Providing and laying Kerb stone of approved manufacturer 3500 PSI (300mmx350mmx150mm) with bed of 1:4:8 P:C:C 3" thick and back side edging 3" thick(1:2:4) complete i/c excavation, compaction and filling of joints with cement mortar 1:2, paint of approved make and colour 3-coats complete in all respect as directed by the Engineer Incharge.	P. Rft	144			
3	Dry rammed brick or stone ballast, 1½" to 2"(40 mm to 50mm) gauge.	P. Cft	180			
4	Providing and laying Tuff pavers, having 7000 PSI, crushing strength of approved manufacturer, over 2" to 3" sand cushion i/c grouting with sand in joints i/c finishing to require slope . Complete in all respect. (50% Grey / 50% Coloured) 60-mm thick.	P. Sft	720			
	Total					
	Add 5% PST					
	Grand Total Amount Rs.					

Sign stamp contractor